

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

11 AUG 1954

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

Ship's Name <b>"FOUNTAINS ABBEY."</b>	Official Number <b>185185</b>	Nationality and Port of Registry <b>BRITISH HULL</b>	Gross Tonnage <b>1100 (APPROX) 1197</b>	Date of Build <b>1954</b>	Port of Survey <b>ABERDEEN.</b>
Moulded Dimensions: Length <b>240.42'</b> Breadth <b>38.5'</b> Depth <b>21.5'</b>				Date of Survey <b>WHILST BUILDING.</b>	
Moulded displacement at moulded draught = 85 per cent. of moulded depth				Surveyor's Signature <i>J. MacLachlan</i>	
Coefficient of fineness for use with Tables <b>.68 (actual .619)</b>				Particulars of Classification <b>100A1.</b>	

<b>DEPTH FOR FREEBOARD (D).</b> Moulded depth ... .. <b>13.50</b> Stringer plate <b>.30</b> ... .. <b>.03</b> Sheathing on exposed deck $T \left( \frac{L-S}{L} \right) =$ Depth for Freeboard (D) = <b>13.53</b>	<b>DEPTH CORRECTION.</b> (a) Where D is greater than Table depth (D—Table depth) R = (b) Where D is less than Table depth (if allowed) (Table depth—D) R = <b>(16.03-13.53) = 2.50</b> <b>= -4.62"</b> If restricted by superstructures	<b>ROUND OF BEAM CORRECTION.</b> Moulded Breadth (B) = <b>38.50'</b> Standard Round of Beam = $\frac{B \times 12}{50} = \frac{462}{50} = 9.24$ Ship's Round of Beam = <b>4.00</b> Difference = <b>5.24</b> Restricted to Correction = $\frac{\text{Diff}^2}{4} \times \left( 1 - \frac{S_1}{L} \right) = \frac{5.24^2}{4} \times 0.124 = 0.82$
--	---	--

DEDUCTION FOR SUPERSTRUCTURES.					
	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)
Poop enclosed ... ..	<b>12.92'</b>	<b>12.92</b>	<b>8.0'</b>		<b>12.92</b>
" overhang ... ..					
R.Q.D. enclosed ... ..					
" overhang ... ..					
Bridge enclosed ... ..	<b>221.50</b>	<b>221.50</b>	<b>8.0'</b>		<b>221.50</b>
" overhang aft ... ..	<b>1.50</b>	<b>1.13</b>			<b>1.13</b>
" overhang forward ... ..					
F'cle enclosed ... ..					
" overhang ... ..					
Trunk aft ... ..					
" forward ... ..		<b>.404 x DIFF</b>			
Tonnage opening aft ... ..	<b>4.56</b>	<b>1.97</b>			<b>1.97</b>
" " forward ... ..					
Total ... ..	<b>240.42</b>	<b>237.52</b>			<b>237.52</b>

Standard Height of Superstructure **6.00'**  
 " " R.Q.D. **✓**  
 Deduction for complete superstructure **30.04"**  
 Percentage covered  $\frac{S}{L} = \frac{100.00}{100.00} = 100.00$   
 " "  $\frac{S_1}{L} = \frac{98.78}{100.00} = 98.78$   
 " "  $\frac{E}{L} = \frac{98.50}{100.00} = 98.50$   
 Percentage from Table, Line A. + B. **98.50**  
 (corrected for absence of forecastle (if required))  
 Percentage from Table, Line B.  
 (corrected for absence of forecastle (if required))  
 Interpolation for bridge less than .2L (if required)  
 Deduction = **30.04 x .9850 = -29.59"**

SHEER CORRECTION.							
Station	Standard Ordinate	S	M	Product	Actual Ordinate	Effective Ordinate	S
A.P. ... ..	<b>34.04</b>	<b>1</b>	<b>34.04</b>	<b>42 3/4"</b>	<b>66.75</b>	<b>1</b>	<b>66.75</b>
1/2 L from A.P. ... ..	<b>15.15</b>	<b>4</b>	<b>60.60</b>	<b>19"</b>	<b>29.70</b>	<b>4</b>	<b>118.80</b>
3/8 L " ... ..	<b>3.75</b>	<b>2</b>	<b>7.50</b>	<b>5"</b>	<b>7.34</b>	<b>2</b>	<b>14.68</b>
Amidships ... ..		<b>4</b>		<b>0</b>		<b>4</b>	
3/8 L from F.P. ... ..	<b>7.49</b>	<b>2</b>	<b>14.98</b>	<b>8"</b>	<b>10.56</b>	<b>2</b>	<b>21.12</b>
1/2 L " ... ..	<b>30.30</b>	<b>4</b>	<b>121.20</b>	<b>32"</b>	<b>42.72</b>	<b>4</b>	<b>170.88</b>
F.P. ... ..	<b>68.09</b>	<b>1</b>	<b>68.09</b>	<b>72"</b>	<b>96.00</b>	<b>1</b>	<b>96.00</b>
Total ... ..			<b>306.44</b>	<b>+24"</b>			<b>488.23</b>

Mean actual sheer aft =  
 Mean standard sheer aft =  
 Mean actual sheer forward =  
 Mean standard sheer forward =  
 Length of enclosed superstructure forward of amidships =  
 " " aft of " =  
 Excess. = **24"**  
 CSS/T.O.

Correction =  $\frac{\text{Difference between sums of products}}{18} \left( .75 - \frac{S}{2L} \right) = \frac{181.82}{18} \left( .75 - .50 \right) = -2.53"$   
 If limited on account of midship superstructure. **✓**

<b>Deduction for Tropical Freeboard.</b> <b>Addition for Winter and Winter North Atlantic Freeboard.</b> Depth to Freeboard Deck = <b>13.53</b> Summer freeboard = <b>.17</b> Moulded draught (d) = <b>13.36</b> Deduction for Tropical freeboard and addition for Winter freeboard = $\frac{d}{4}$ inches = <b>3.34 = 3 3/4"</b> Addition for Winter North Atlantic Freeboard (if required) = <b>3 3/4 + 2 = 5 1/4"</b>	<b>Deduction for Fresh Water.</b> Displacement in salt water at summer load water line $\Delta = 2276$ Tons per inch immersion at summer load water line $T = 17.37$ Deduction = $\frac{\Delta}{40 T}$ inches = <b>3.28 = 3 1/4"</b>	<b>TABULAR FREEBOARD</b> corrected for Flush Deck (if required) Correction for coefficient <b>NIL</b> Depth Correction ... .. <b>4.62</b> Deduction for superstructures ... .. <b>29.59</b> Sheer correction ... .. <b>2.53</b> Round of Beam correction ... .. <b>.02</b> Correction for Thickness of Deck amidships ... .. Other corrections, scantlings, etc. ... .. <b>.02 36.74 - 36.72</b> Summer Freeboard = <b>6.34</b>
--	---	--

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, ~~Work~~ Steel, Deck :-

Tropical Fresh Water Line above Centre of Disc ...	<b>3 3/4"</b>	Tropical Fresh Water Freeboard MINUS 1 1/4"	<b>2" (LIMITED)</b>
Fresh Water Line " " ...	<b>3 3/4"</b>	Fresh Water " " MINUS 1 1/4"	<b>2" (LIMITED)</b>
Tropical Line " " ...	<b>NIL</b>	Tropical " " " " " "	<b>2" (LIMITED)</b>
Winter Line below " " ...	<b>3 3/4"</b>	Winter " " " " " "	<b>5 1/4"</b>
Winter North Atlantic Line " " ...	<b>5 1/4"</b>	Winter North Atlantic " " " " " "	<b>7 1/4"</b>

# Fountains Abbey.

A new form should be prepared if any alterations that affect the freeboard have been made. If no such alterations have been made, the Surveyor should endorse the form on this side with his signature and the date.

MOULDED DRAUGHT	Δ MLD	Δ EYT	T.P.I.
18.275	3320	3339	19.2
12.5	2086	2102	17.04
12.0	1985	2001	16.85
11.5	1885	1901	16.66
11.475	1880	1895	16.65
11.0	1785	1800	16.47
10.5	1687	1702	16.28

$$\frac{B_1 - B_2}{B_1} = \frac{28.5 - 17.0}{28.5} = \frac{11.5}{28.5} = .404$$

Trade of ship CARGO.

Names of sister ships "WHITBY ABBEY" (HALL RUSSELL & CO YARD N° 838)

Builder's name and yard number MESSRS HALL RUSSELL & CO YARD N° 839.

Owners ASSOCIATED HUMBER LINES LTD.

Fee £ TO BE CHARGED WITH FIRST ENTRY.



© 2020

Lloyd's Register  
Foundation