

Lloyd's Register of Shipping.

Ship's Name *S. S. "GWENTHILLS"*Official No. *162144.*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1937.

New accommodation for additional gunners fitted out in rooms in the existing machinery casing house and in new steel house built on casing top.

Two new 6" dia. mushroom ventilators with screw down tops fitted on the casing top. Five new 16" dia. cast brass escape scuttles having cast iron deadlights have been fitted, one on the forecastle end bulkhead, one on the bridge front bulkhead, two on the machinery casing house starboard side and one on the machinery casing house port side. One new watercloset and two new washbasins have been fitted in the casing house starboard side arranged to discharge overboard thro' a 4" dia. soil pipe having automatic non return valve fitted on the shell plating below the Quarter Deck. One new escape hatch from engine room fitted on the casing top port side, opening 24" x 24" having a 5'-3'- $\frac{7}{8}$ " angle coaming riveted to casing top, $\frac{1}{4}$ " thick rubber jointed watertight hinging steel cover fitted with toggles capable of being operated from both sides.

A copy of this report to be placed on board the vessel.

Alex. M. Jenkins.

noted

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING

LONDON.

13TH FEBRUARY 1943.

17 FEB 1943



© 2020

Lloyd's Register
Foundation