

## Lloyd's Register of Shipping.

Ship's Name "SEMINOLE"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in

Items not on Rpt C11

Two derrick post vents on freeboard deck at forward end of after well, 24" diam  
and about 30' high, fitted with cowl tops but not fitted with closing appliances.  
These lead to the pumproom.

One ventilator on freeboard deck at forward end of forward well, port side, 22" diam  
and about 14" high, fitted with cowl top but not fitted with closing appliances.  
Six gooseneck ventilators (to lamproom stores, etc.) port and starboard, fitted  
on the forecastle deck and provided with hinges watertight covers, secured by toggles.  
Companionway entrance in after end of house on poop deck. Opening closed by hinges  
W.T. steel door operated from both sides. Door sill 18" high.

Copy placed on board. Sd. A. Reed.

Noted. [Signature]

21 DEC 1942

