

COPY

London

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER



*Damage Rs. 100/-
Exps. -*

Port

CALCUTTA

28th December, 1960.

This is to Certify that

A. R. MORTON.

the undersigned Surveyor to this Society did at the request of

the Owners representative survey the S.S. "JAG JANANI" 6144 tons gross of Bombay on the 12th December 1960 and subsequently whilst the ship was afloat at Calcutta for the purpose of ascertaining the nature and extent of damage stated to have been sustained while at Garden Reach Anchorage, River Hooghly, on the 10th December 1960, when the vessel was required to go astern on the engines while at anchor to avoid M.V. "DINARA" approaching her bows.

For further particulars see Log Books.

Damage confined to steam windlass.

The undersigned upon examination

FOUND

RECOMMENDED

Windlass cast iron bedplate, two aftermost portions, containing the steam cylinder casting seating and the brake anchor bolts, broken off.

Bedplate to be renewed.

Wood sheathing splintered below after part of windlass bedplate.

Wood to be renewed.

Starboard crankpin slack.

Crankpin to be renewed.

Steam cylinders and valves.

To be opened for examination.

Two forecastle deck plates slightly set up in way of windlass brakes anchor bolts.

Two deck plates to be faired in place.

/2...

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :—

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."


COPY

Lloyd's Register of Shipping.

- 2 -

S.S. "JAG JANANI"

The above recommendations have been made in order to place the ship in as good a condition as she was in before the alleged casualty. Temporary repairs have been carried out to my satisfaction. Permanent repairs have been deferred until the vessel's arrival in Bombay during the present voyage.



SURVEYOR TO LLOYDS REGISTER OF SHIPPING.



© 2020

Lloyd's Register
Foundation

0013²/2