

13 MAY 1946

Lloyd's Register of Shipping.

Ship's Name S.S. "CITY OF BARCELONA" Official No. 168748

Memorandum of alterations ^{in connection with reopening.} ~~reported since ship was surveyed for assignment of load~~
~~line~~ shelter deck.

All middle line openings restored in shelter deck bulkheads port and starbd. sides at frames 126, 88, 81, 58 port side 60 starboard side, 30 and 18 at tonnage opening. All openings 3 feet 6 inches by 5 feet with 18 inch sills except tonnage openings at frames 18 which are 5 feet 7 inches by 4 feet with 17 inch sills.

All openings have been fitted with portable steel plates fastened with hook bolts. The permanent closings of the tonnage hatch have been removed and wood covers 6 feet by 20 inches by 2 1/2 inches without permanent means of closing have been fitted.

The freeing ports in the tonnage well 2 feet 9 inches by 1 foot 3 inches have been restored in the vessels sides, area 3.4sq. feet, and hinged shutters fitted, height above deck cope 4 inches, position midway in tonnage opening.

scuppers leading overboard and fitted with storm valves have been fitted at after ends of Nos. 1,2 and 3 tween decks and fwd. ends of No.5 tween decks and tonnage opening, scuppers of bunker tween deck and No.4 tween deck (above deep tank) are led to engine room bilges. *X Self closing cocks.*

John Jones

W. J. J.

18 JUL 1946



© 2020

Lloyd's Register

Foundation

002750-002753-0038