

Lloyd's Register of Shipping.

2nd 4742

Ship's Name "RABY CASTLE".

Official No. 147306.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

CLOSING OF TONNAGE OPENING.

The tonnage opening has now been permanently closed by fitting a welded steel plate supported with one 6" x 3" angle beam bracketed to coaming.

A small entrance hatch fitted to tonnage well (P.S) 2'0" x 1'9" with 30" plate coaming and fitted with steel W.T. cover in accordance with rule requirements.

The freeing ports and all overboard scuppers from the tween deck spaces now permanently closed with welded steel plates.

Suitable provision made for the rigging of lifelines available in all parts of the ship for use of the crew in the regular working thereof.

The deadlights of all side scuttles in cargo spaces below the shelter deck secured by special nuts which cannot be operated without the consent of the master.

3" scupper pipes now fitted from tween decks on each side of the ship at the fore and aft ends of the machinery space.

Freeboard marks verified.

Rockland

SURVEYOR TO LLOYD'S REGISTER.

W. H. R.
14/9/42



© 2020

Lloyd's Register
Foundation