

1000

Glasgow

LAKE FREEBOARDS

Alterations Required In Order To Comply With
Conditions of Assignment

SS "CALGARIAN"

- After deckhouse - Strong shutters required for windows.
- Four 1-1/2" panel wood doors require to be plated (on account of engine casing being open at fore end - hinged cover on Engine Room stairway not sufficient protection.)
- Fiddley covers require repairs.
- Deckhouse front stiffeners require repairs.

- Forecastle - Strong shutters required for 2 windows in bulkhead.
- Metal covers required for sidescuttles.

- Hatches - Securing bars required for each hatch.

- Discharges - Bath (on 2nd deck aft - in Engine Room) drain requires positive action valve.

- Lifeline - To be provided.

- Vents & Airpipes - Means of closing to be provided as required.



© 2021

Lloyd's Register
Foundation

002816-002824-0031