

002816-002824-0162

D B 208

"CABO TORINANA"

This ship was built by Grangemouth and
Shoch Dockyard Co. in 1903-11 when she was classed
OAL "Awning deck with freeboard".

The class was expunged with a red line in 1940.

At Owners' request a 3rd S.S. No.3 for
classification was commenced at Bilbao 12,41, but never
completed.

Owners, through the Bilbao Surveyors again
request Reclassification, and in a cablegram received
11.52 desire plans of Midship Section and Profile & Decks
approval of Owners' request, and in reply IT IS SUBMITTED
to be informed that in order to have her character
restated in the Register Book as formerly, it will be
necessary for:-

- (1) the requirements of a PERIODICAL SPECIAL SURVEY (D)
to be complied with, which includes the drilling
of the shell plating amidships, in the vicinity
of the peaks, the strength deck amidships, and in
such parts of the structure where signs of wastage
are evident. The particulars of shell and deck
thicknesses as ascertained should be forwarded
for the consideration of the Committee as soon
as possible.
- (2) Any major repairs which have been effected to
the structure since the ship was disclassed to
be specially examined in order to ascertain
the character of the workmanship and confirm that
the materials used are in accordance with the Rules.
- (3) Structural alterations which may have been carried
out since the ship's class lapsed and which affect
the longitudinal and/or transverse strength of the
ship to be reported.
- (4) Full particulars of the equipment on board to be
furnished so that the Figure '1' can be reinstated,
and
- (5) the Special Survey to be held at a port where the
Society is represented in view of the age of the
vessel and the importance of the Survey.

A photostat copy of the Midship Section and
Profile and Decks plans to be forwarded to the Surveyors
requested.

11.1.52.

The requirements of a Special Survey on the
machinery and boilers would require to be carried out,
including the examination and testing of the steam pipes
and the examination of the screwshaft.

For ¹⁸⁶⁰ ~~the~~ (H).
Fuhin (S) for ¹⁸⁶⁰ ~~the~~ (H) X 11.1.52.