

C. 7c, 11.28.

FREEBOARD REPORT on the

"Whitwood"

It is submitted the Freeboards given on the accompanying

- form, being those required by the Tables, merit approval, subject to :-
- ① Ventilator coamings, on Freeboard and Raised Quarter Decks, which are more than 36 inches in height, being efficiently supported if not already the case.
 - ② A gangway, lifelines, or other efficient means being provided, in the fore well, for the protection of the crew.
 - ③ Fencing port area in bulwarks of Raised Quarter Deck being increased to $16\frac{1}{2}$ square feet on each side of ship.
 - ④ A screw cap, being fitted to the flush air pipes on the raised quarter deck from the after tank & satisfactory means of closing being provided for the air pipes where this is not already the case.
- The Convention Summer Freeboard being the same as the existing summer freeboard, and the Convention Winter Freeboard being in excess of the existing winter freeboard, the existing freeboards have been reassigned.

Convention is Owned 14/5/32

002816-00284-0250