

N^o 329
MIDSHIP SECTION
DIMENSIONS - 46'-0" B.P. x 61'-0" M^{LD}. x 33'-3" M^{LD} TO UPPER D.K.
SCALE - 1/2" = 1 FOOT

1 st Longitudinal N°	L x D	460.0" = 33.25	= 15295.00
2 nd "	"	L x (B + D)	460.0 x (61.0 + 33.25) = 43355.00
1/2 to Upper Deck	=	460.0 ÷ 33.25	= 13.83
		D	= 33.25

2 nd Long ¹ N° Lx(BxD)	= 43355.00
Poop 105.33x7.5 x ³ / ₄	592.50
Bridge 43.16x7.5 x ³ / ₄	242.70
Forecastle 38.5x7.5 x ³ / ₄	216.57
House on Poop Deck 82.5x7.5 ÷ 2	309
House " Bridge " 120 x7.5 ÷ 2	450
Equipment N°	45165.77

2 Bower Anchors 73% Cwts Each Stockless
 1 Steam " 22 " Ex Stock
 240 Fathoms 2 1/2" Stud Chain Cable (Tayed)
 120 " 5" Flexible Steel Wire 6x12
 130 " 5 1/2" Special Flexible Steel Wire 6x24
 2 Hawsers 100 Fathoms 2 3/4" Steel Wire 6x12
 2 Warps 100 " 2 3/4" " " 6x12

Bilge Radius 5'-0"
Bilge Keel
6 1/2 x 6 1/2 x 5/8 Tee Bar
10 x 1 1/2 Bulb Plate

Bottom Shell .70" in way of Longth. Framing
-.06" at Normal Spacing to .50" at Ends.
Butts Quad^{la} Riveted Overlaps for 1/2 L to Treble at Ends

Bottom Longitudinals 17" x .58" x 4" x 4" x .68" Channels

53" x .97" to .77"
Butts Quintle Overlaps for $\frac{1}{2}L$
to Quadle at Ends.

Centre Girder Plates fitted
Intercostally between
Transverses

№ Т 4460.

002830 - 002837 - 0073

MIDSHIP SECTION

AS BUILT

FURNESS S.B. CO. LTD


No 329.

EMPIRE SAPPHIRE

N/N ESSO SARAVAC

0073

ESSO. Saravac



© 2021

002830-002837-0073

Loy's Register
Foundation