

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.

Signal Letters (if any) **V.P.L.M.**

Official Number.	Name of Ship.	No., Date, and Port of Registry.
156,140.	Jamaica Producer.	1 in 1934 Kingston, Jamaica.

No., Date, and Port of Previous Registry (if any). **First Registry.**

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	Port Glasgow.	1934	Livingtons Limited Kingston Shipbuilding Yard, Port Glasgow.
Number of Decks ..	Four	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ..	Feet. 411	Tenths. 1
Number of Masts ..	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ..	410	1.2
Rigged ..	Schooner	Main breadth to outside of plank .. plate ..	54	7.5
Stern ..	Cruiser	Depth in hold from tonnage deck to ceiling at midships ..	30	3.5
Build ..	Clinker	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ..	34	6.2
Galleries ..	None	Depth from top of beam amidships to top of keel ..	33	6.8
Head ..	None	Depth from top of deck at side amidships to bottom of keel ..	1	1
Framework and description of vessel ..	Steel Cargo	Length of engine room, if any ..	80	0
Number of Bulkheads ..	Eight			
Number of water ballast tanks, and their capacity in tons	5 in D.B. - 773 Tons Aft Peak - 70 Tons Fore Peak - 31 Tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel. **10202** Tons. Ditto per inch immersion at same depth **41.6** Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Reciprocating Steam Direct Acting Vertical Inverted Cylinder, Quadruple Expansion.	Engines.	Engines.	Engines.	Four 30" 41 1/2" 59" 84"	54"	----	961 5,500 16 Knots
One	Particulars of Boilers. Description Horiz. R.T.S.E. Number Five Iron or Steel Steel Loaded Pressure 225 lbs	Boilers.	Boilers.	Boilers. David Rowan & Co., Ltd., Glasgow.				

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ..	4673.07	On account of space required for propelling power	2052.61
Space or spaces between Decks ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	256.96
Turret or Trunk ..	73.25	These spaces are the following, viz: Houses in Forecastle & in Round Houses above Upper Deck	
Forecastle (5 Houses in) ..		(Number of Seamen or Apprentices for whom accommodation is certified.....59.....).	
Bridge space ..		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Poop or Break ..	565.17	Master's Accommodation-14.23)	
Side Houses ..	7.39	Chart Space - 7.39)	
Deck Houses ..		Wireless Telegraphy - 3.30)	80.27
Chart House ..		Boatswain's Store - 27.01)	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ..	6.32	Water Ballast Spaces - 28.34)	
Excess of Hatchways ..		Total ..	2389.84
Gross Tonnage ..	5325.20	Cubic Metres.	
Deductions, as per Contra ..	2389.84	15070.32	
Register Tonnage ..	2935.36	6763.25	
		8307.07	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **1172.92** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **146.75** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open space in Forecastle 48.9 feet in length - 20.97 tons.

Name of Master **Geoffrey Wilday Boddie**

Certificate of { Service Competency No. **006057**

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.


Jamaica Banana Producers Steamship Company Limited
64, Harbour Street,
Kingston, Jamaica, Sixty-Four Shares.

Dated **29th June, 1934.**

*826. Wt. 11709/390. 2,000. 9/32. Wy.P.C. Gp. 613.

002838-002845-0169

Manufacturer.



002838-002845-0167

Lloyd's Register
Foundation