

Boilers made at
Registered Horse Power

By whom made
Owners Jamaica Banana Producers S.S. Co. Ltd.
Is Refrigerating Machinery fitted for cargo purposes Mes

Boiler No.
Port belonging to
Is Electric

Rpt. 7.

For the information of Surveyors and the Committee only.

Received at _____ Office, _____ 19__

Lloyd's Register of Shipping.

(Report on Machinery, No. 54627 Port GLASGOW)
Jamaican Producer

No. 4684 ENGINE FORGINGS OR CASTINGS.

I have to report that the Forgings or Castings, as herein described, manufactured by Messrs. D. Rowan & Co. Ltd of Glasgow for the Engines No. 965 being constructed by Themselves of _____ for the Ship No. 868, being built by Messrs. Lithgow & Co. Ltd. of Port Glasgow have been inspected by me as set forth below, and found to be, so far as can be seen, sound and free from defects. These have been despatched to Themselves.

The words FORGINGS or CASTINGS should be struck out as may be required.

Mark on Forgings or Castings.

Lloyd's
No. 4684
C.S.P.


Chas. S. Porter
Glasgow. 4/10/1933

	CRANK SHAFT. <u>Piston Rods</u> <u>4. 6H.</u>	THRUST SHAFT. <u>Crossheads</u> <u>4. 6H.</u>	INTERMEDIATE SHAFT.	TUBE SHAFT.	FLYWHEEL SHAFT.	SCREW SHAFT.
Material* ...	<u>Siemens Martin Engot Steel</u>		/			
How made ...	<u>Forged.</u>					
Annealed ...	<u>Yes.</u>					
Dimensions, Forgings	<u>As. per app. plan</u>					
Weight, Castings						
Progress on Inspection	<u>Forging and Testing.</u>					
Tests on Standard Test Pieces.	<u>Test No's</u> <u>53. 54. 55</u>	<u>Test No's</u> <u>56 57</u>				
Tensile Test— Tons per square inch	<u>31.4 32.0 31.0</u>	<u>30.6 28.9</u>				
Extension per cent	<u>36 34 31.5</u>	<u>33 36</u>				
Cold Bending Test— Angle before fracture	<u>180 180 180</u>	<u>180 180</u>				
Dates when Inspected	<u>8/9/33 to 28/9/33</u>					

PARTICULARS OF OTHER TESTS APPLIED TO CASTINGS:—

Fee (if any chargeable) £ NIL (Vessel Classed) To be paid at LC.D.

* If of wrought iron, state whether piled bars or scrap. If of steel, state whether made by the Open Hearth process.



002838-002845-0175

Manufacturer.