

-7 AUG 1941  
34372

## Lloyd's Register of Shipping.

Ship's Name "JAMAICA PRODUCER"

Official No. 156140

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

New hatchway fitted 6,41 inside after deckhouse. Forward coaming 14'2" abaft the forward bulkhead of the deckhouse. Side coaming 6½" inside the port side of the deckhouse. Dimensions of hatchway 49" x 55". Coamings 10" above deck, thickness sides and ends 7/16". Deck angles 7/16" x 3" x 3". Spacing of cleats 21". Hatch covers pitch pine 2⅜" thick fitted fore and aft with a bearing surface of 3".

Noted *[Signature]**Edgar Wilson.*

-7 AUG 1941



© 2020

Lloyd's Register  
Foundation

002838-002845-0194