

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
K.V.M.B.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
49,746.	Southgate.	163 in 1926 London.

Date, and Port of Previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw	South Shields	1926	John Readhead and Sons Limited, South Shields.

Number of Decks ...	Two	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	400	0
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	400	0.5
rigged ...	Schooner	Main breadth to outside of plank ...	55	2
Plan ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	25	7.5
Side ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	--	--
Series ...	None	Depth from top of beam amidships to top of keel ...	29	3
Material ...	None	Depth from top of deck at side amidships to bottom of keel ...	28	4.7
Framework and description of ...	Steel	Round of beam ...	1	0.5
Vessel ...	Cargo	Length of engine room, if any ...	49	0
Number of Bulkheads ...	Six			
Number of water ballast tanks, ...	Six -			
and their capacity in tons ...	1399 Tons.			

PARTICULARS OF DISPLACEMENT.

Weight to quarter the depth from weather deck at side amidships to bottom of keel ...	13420 Tons.	Ditto per inch immersion at same depth ...	44.7 Tons.
---	-------------	--	------------

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
Triple expansion Direct Acting Inverted Cylinders	Engines. British	Engines. 1926	John Readhead and Sons Limited.	Three 27"	48"	---	456
Cylindrical Multitubular	Boilers. British	Boilers 1926	South Shields.	44" 73"			2600
Number ...							10.8 knots
Iron or Steel ...							
Loaded Pressure ...							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	4543.67	On account of space required for propelling power	1555.92
On account of spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	213.19
On account of Trunk ...	23.28	These spaces are the following, viz.:—	
On account of ...		(No. of Seamen or Apprentices for whom accommodation is certified 45)	
On account of ...	131.02	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
On account of ...	164.28	Masters Accommodation 14.43	
On account of ...		Cubic Metres Boatswains Store Room 48.62	
On account of ...		Wireless Telegraphy House 4.30	122.15
On account of ...		Chart Space 5.66	
On account of ...		Water Ballast Spaces 49.14	
On account of ...		Total ...	1891.26
Gross Tonnage ...	4862.25		
Deductions, as per Contra ...	1891.26		
Register Tonnage ...	2970.99		

1.—The tonnage of the engine room spaces below the Upper Deck is 663.76 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 121.84 tons.

2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Passages on Shelter Deck (Starboard)	L. 38.0' - 20.42 Tons
(Port)	L. 40.0' - 21.17 "
Shelter Deck Part I	L. 333.4' - 1161.17 "
Part II	L. 9.4' - 35.08 "

Name of Master	Certificate of { Service No. Competency No.
----------------	--

Name of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

Turnbull Scott Shipping Company Limited,
24, St. Mary Axe,
London.

Shares: Sixty-four
dated 3rd November 1926.

Reginald March Kesterson Turnbull of
Exchange Chambers,
24 St. Mary Axe, London, E.C.3.
-Manager-