

## Lloyd's Register of Shipping.

12 MAY 1941

Ship's Name "SOUTHGATE".

Official No. 149746.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

New freeboards have been assigned to this vessel and the following alterations have been carried out.

The tonnage opening in the shelter deck, the freeing ports in the tonnage well and all overboard scuppers draining the shelter 'tween decks (including those in the tonnage well) have been permanently closed. ✓

Adequate provision has been made for rigging lifelines. 1 ✓

The exposed machinery casings on the shelter deck have been reinforced with additional vertical stiffeners. ✓

Rider plates 7" x 60" have been fitted to the lower mounting angles on No. 3 Hatchway beams. ✓

A scupper has been fitted from the tween decks port and starboard at forward and after ends of machinery space draining to the machinery space bilges.

The watertight bulkheads do not extend to the shelter deck.

Gunners accommodation has been fitted in the original tonnage well space & the following alterations have been effected.

A Lavatory has been fitted discharging above the 2nd deck.

Discharge fitted with a storm valve and a gate valve, geared, and capable of being operated above the freeboard deck. ✓

2 Portlights on shell on starboard side and 1 on Port side of strong construction with hinged deadlights. ✓

1 scupper from Gunners' accommodation P. & S. draining to the tunnel well. ✓

New companionway fitted aft 6'-3" high x 4'-5" x 3'-0" strong wood door 4'-1" x 24" Sill 21". ✓

2 ventilators 3'-0" high x 6" dia. x .36" thick. 2 Bogey stove coamings 3'-0" high x 3½" dia. x .32" thick. Wood plugs and canvas covers provided. ✓

2 circular lights fitted on deck aft of strong construction. ✓

The openings in tonnage well bulkhead have been plated over. ✓

*S. S. Lumsden*

SURVEYORS TO LLOYD'S REGISTER.

*Noted  
12/15/41*

*W. S. Lumsden*

*W. S. Lumsden*

*W. S. Lumsden*