

Lloyd's Register of Shipping.

Ship's Name

"FORDSDALE"

Official No. 151988

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in 1932

- 1) Tonnage opening on the shelter deck permanently closed by fitting a B.A. beam and wood decking caulked and payed. ✓
- 2) Wash ports in the tonnage space permanently closed by riveting plates over the openings. ✓
- 3) All overboard scuppers from the shelter tween decks permanently closed by welding plates over the openings at the shell, and the tween decks are efficiently drained to the bilges. ✓
- 4) The present battening arrangements of the shelter tween deck hatchways are being maintained and are efficient. ✓
- 5) Side scuttles in the forecastle are fitted with hinged deadlights. ✓
- 6) Efficient lifelines are provided in all parts of the ship. ✓
- 7) The statutory deck line has been cut in at the level of the steel shelter decks, and the freeboard reassigned. ✓

Arthur N. Smith ✓

11/12/39

A copy of the above memorandum has been placed on board the ship. ✓

No alterations have been effected to the tonnage space Bulkheads.

New gross tonnage = 11022.68

Reg. depth = 41.2'

" nett " = 6740.98

