

Lloyd's Register of Shipping.

Ship's Name "*FORDSDALE*"Official No. *151988*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in *DECEMBER 1939*

- ① Tonnage opening in Shelter Deck reopened. Existing wood decking and B.A. beam removed, and hatch fitted with closing appliances as originally. ✓
- ② The Statutory deck line has been cut in at the level of the second deck, and the freeboard reassigned. ✓
- ③ All hatchways on second deck have coaming, covers and battening arrangements in accordance with the Rules. ✓
- ④ The tonnage well is drained overboard by 5" scuppers fitted pas and provided with S.D. automatic N.B. valves controlled from shelter deck and having indicators to show whether the valves are open or shut. ✓
- ⑤ All overboard scuppers from shelter tween decks have been fitted as originally with automatic non return valves and have had their closing plates removed from shell. ✓
- ⑥ All existing scuppers draining shelter tween decks to bilges have been permanently closed by welded plates. ✓

A copy of this report has been placed aboard the vessel.

A. Jas. Smith.
London

4th June 1948.

Noted
9th JUN 1948