

Kaiser Co. Inc., Portland, Oreg.

Yard No.

T2 TANKER.

to Chief Surveyors.....

Received from Chief Surveyors.....

SEL'S NAME 'THELIDOMUS'

REPORT Liv. No. 127333

For the CHIEF SHIP SURVEYOR and -CHIEF-ENGINEER-SURVEYOR----

In cases which have to be submitted to the Classing Committee "the endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case so that the Classing Committee may have all the salient points presented in the endorsement."—(Extract from Sub-Committee's Report, 24/5/92.)

COMPLETION OF S.S. FOR CLASSIFICATION, ALTERATIONS AND REPAIRS.

e of Survey.....

When due.....

This tanker was built in 1944 and classed with the American Bureau of Shipping.

The vessel has the temporary class 100A1 "Carrying Petroleum in Bulk" (Classification Contemplated) assigned and notation of "Examined 9.47".

These notations are subject to No. 3 tank being tested before different grades of oil are carried in Nos. 2 & 3 tanks and to the equipment being brought up to Rule requirements.

The Classification Survey was commenced at Liverpool in September 1947.

For full particulars of this case see previous endorsement.

The LIVERPOOL Surveyors report the vessel placed in dry dock, the SPECIAL SURVEY FOR CLASSIFICATION completed and repairs effected.

The shell and deck plating have been cut and strapped at this time.

No. 3 tank, as above, now dealt with.

The vessel has now on board 3 bower anchors, 1 stream anchor and 265 fathoms of chain cable, which is 65 fathoms below Rule requirements, and it is recommended this be supplied at the first opportunity.

The equipment has now been retested by Surveyors of this Society.

"Subject to 60 fathoms of chain cable being supplied at the first opportunity".

100A1 "Carrying Petroleum in bulk"


"Fitted for oil fuel, F.P. above 150°F".

6.48 Bkn. ) subject

S.S. Bkn.- 6.48 ) without

Classed 6.48

(when MS completed)



© 2020

Lloyd's Register  
Foundation

002858-002869-0249 1/2



'THELIDOMUS'

1 Dk, 2nd dk inway of mchy space. "Elec.welded" "Longitudinal framing".

Cell DBuE 82' 273t, DTf 32' 745t, FPT 314t, APT 56t.

FK. 14BH. "Lloyd's A & CP".

P 108', B 36', F 56'.

Mchy Aft

O.L. 523.5

ESD

2.5/16" ✓

Equipment letter for fees: "g†" in red.

C.S.S. Records Dept.

to note. Fractures.



WOT.

3.9.48.

recd. [Signature]



© 2020

Lloyd's Register  
Foundation

002858-002869-0249 2/2