

"THELIDOMUS"

AND

"TENAGODUS"

The equipment letter for this type of tanker has been taken out and is g^t.

IT IS SUBMITTED the Owner's be informed the Rule requirements are as follows:-

- ✓ 3 bower anchors of 271 cwts. collective weight (stockless).
- ✓ 1 stream anchor, 28 cwts. (ex.stock).
- ✓ 330 fms. 2 $\frac{11}{16}$ " dia. wrought iron, or 2 $\frac{5}{16}$ " special steel, stud chain cable.
- ✓ 120 fms. 1 $\frac{9}{16}$ " stream chain or 5 $\frac{1}{2}$ " 6 x 24 Special flexible steel wire rope.
- ✓ 130 fms. 6 $\frac{1}{2}$ " Special flexible steel wire towline.
- ✓ 2 x 100 fms. 8" hemp or 2 $\frac{3}{4}$ " 6x12 flexible steel wire hawsers.
- ✓ 2 x 100 fms. 8" hemp or 2 $\frac{3}{4}$ " 6 x 12 flexible steel wire warps.

ABM.
11-11-47.

ABM.

It is further submitted the Owners be informed the anchor & cable equipment reported on board 9,47 consists of,

Bower anchor 11,700 lbs. (stockless)

" " 11,740 " "

" " 11,740 " "

Stream " 4340 "

270 fms. 2 $\frac{5}{16}$ " H.T. stud chain cable.

© 2020

Lloyd's Register
Foundation

002858-002869-0275