

Glasgow.  
Copy of list sent to owners

LAKE FREEBOARD

1596

ALTERATIONS REQUIRED IN ORDER TO COMPLY WITH

CONDITIONS OF ASSIGNMENT

S/S "KINMOUNT"

Deckhouse Aft - Strong shutters to be provided for windows. 4 doors to be plated (strap hinges) and sills to be raised to 18" or hinged steel cover with angle coaming, to be fitted over one open stairway to Engine Room.

Ventilators & Airpipes - All to be provided with wood plugs and canvas covers.

Lifelines - To be fitted.

Hatch beams - Existing wood fore and afters (8 x 8) have less than 50% of the Rule strength required.  
(Rule wood beams would be about 12" x 9" (12" Vertical))  
Recommend fit steel fore and afters as follows;-

Nos. 1, 3, 4 and 5 hatches - Three @ 12" x 5" x 31.8# I Beams (or equivalent).

Nos. 2 and 6 hatches - Five @ 12" x 5" x 35# I beams.

Thwartship beams - Nos. 1, 3, 4 and 5 hatches - 7 x 7 wood required instead of existing 6 x 6.

Nos. 2 and 6 hatches - existing 6 x 6 beams - in order.

Carriers for steel beams should be renewed throughout of  $3\frac{1}{2}$  x  $3\frac{1}{2}$  x  $\frac{1}{2}$ " angle.

© 2020  
Lloyd's Register  
Foundation

002858-002861-0200