

Kaiser Co. Inc., Portland, Oregon.

Yard No. 145.

T2 Type Tanker.

to Chief Surveyors

Received from Chief Surveyors

VESSEL'S NAME 'THEOBALDIUS'
(ex 'Silver Creek')

REPORT Gal. No. 5005

For the CHIEF SHIP SURVEYOR and ~~CHIEF ENGINEER-SURVEYOR~~

In cases which have to be submitted to the Classing Committee "the endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case so that the Classing Committee may have all the salient points presented in the endorsement."—(Extract from Sub-Committee's Report, 24/5/92.)

Completion of S.S. for Classification, Alterations and Repairs.

Nature of Survey

This tanker was built in 1945 and classed with the American Bureau of Shipping.

The vessel has the temporary class 100A1 "(Classification Contemplated)" assigned and notation of "Examined 10.47".

The GALVESTON Surveyor, in a First Entry Report and Rpt. 8, reports 6.48 the vessel placed in dry dock, the scantlings and arrangements verified, the requirements for Vessels Not Built Under Survey and of a Periodical Special Survey complied with.


The deck, bottom and side shell have been cut and strapped at this time.

The vessel has now on board 3 bower anchors, ^(above Rule weight) 1 stream anchor and 300 fathoms of chain cable, which is 30 fathoms below Rule requirements, and it is recommended this be supplied at the first opportunity.

The equipment has been tested by the American Bureau of Shipping and, it is submitted, can be accepted for the figure "1", the notation of Lloyd's A & CP being omitted.

"Subject to repairs to indented shell plating (p.s.), to oil gutterways being fitted in E.R. and to 30 fathoms of chain cable being supplied at the first opportunity".

100A1 "Carrying Petroleum in bulk"

"Fitted for oil fuel FP. above 150°F". *Enk.*

6.48 Gal.

S.S. Gal.- 6.48.

Classed 6.48.

1 Dk, 2nd dk in way of mchy space, "Elec.welded", "Longitudinal framing".
Cell DBuE 82' 238t, DTf 32', 759t, FPT 314t, APT 60t.

FK, 14BH

P 108, B 36', F 56'

Mchy Aft

O.L. 523.5'


ESD

2 5/16"

Equipment letter for fees "gt" in red.

C.S.S. Records Dept.

to note. Fractures.



© 2020

Lloyd's Register
Foundation

24.8.48.

002870-002875-0032