

Ex German Steamer 'Wilhelm Demuth.'

This vessel built in 1908 by Messrs Nordseewerk Eider Werft & Dock A. G. Emden, was classed with the Germanischer Lloyd, and is now at Middlesbrough undergoing survey with a view to classification with this Society.

A plan of the main boilers has now been forwarded for consideration. The scantlings as shown on plan meet the requirements of the Rules for the original working pressure of 185 lbs per square inch, with the exception of the percentage strength of the longitudinal seam which is slightly under that required by the Rules for this pressure.

It is submitted that provided the boilers be examined and found in good order and safe working condition; their scantlings be in accordance with the plan, they might be approved for the original working pressure of 185 lbs per square inch.

The Middlesbrough Surveyors should be advised accordingly and be requested to forward particulars of the cylinder diameter, length of stroke, shafting, diameter of propeller and a plan of the pumping arrangements, and also state whether the screw shaft is fitted with a continuous liner or otherwise.

Return 1 plan

L1: 24/11/20

Early reply requested.

002883-002890-0018



2020

Lloyd's Register  
Foundation