

S.S. "CITY OF DIEPPE" - Class:- 100A1.  
-----

Present Dimensions:- 465' x 58' x 34.92'  
-----

A plan, in duplicate, has been forwarded by Messrs. Wm. Gray & Co.Ltd., shewing a proposal to lengthen this vessel by 16'-6" on the load water line by fitting a bow of "Maier" form.

The form of the bow is such that with the length increased as proposed there will be no sensible increase to the displacement, and having regard to the fact that this is an existing vessel, it is considered that, as in previous similar cases, no additional strengthening need be required.

The equipment number is increased by one grade, and it is considered that one additional 15 fathom length of cable should be supplied to make up for the deficiency in this respect.

It is therefore submitted the Middlesbrough Surveyors be informed that no additional stiffening to the hull will be required if the vessel be altered at the forward end as shewn on the plan, but that the equipment should be increased by one 15 fathom length of cable.

If the alterations are to be proceeded with detailed plans should be submitted for consideration.

*J.M.M.* *W.J.*

© 2020 34.



Lloyd's Register  
Foundation

002897-002906-0107

*Ltr. 13/3*  
*1 plan returned*