

SCALE:- $\frac{1}{2}" = \text{ONE FOOT}$

DIMENSIONS.

NUMERALS.

PROPORTIONS DEPTH TO SHELTER DK 10.99

EQUIPMENT NUMBER.

54.5	$\times 36.50$	$\times 4.01$	=	36491
FORECASTLE	285	$\times 7.12$	$\times 75$	= 152.19
HOUSES	247	$\times 75$	$\times 5$	= 92.62
CASING	68.5	$\times 7.75$	$\times 5$	= 265.44
				37001.25

EQUIPMENT.

2 BOWER ANCHORS	EACH	63 ³ / ₄ CWTs	STOCKLESS
1 STREAM ANCHOR		14 ¹ / ₂	EXCLUDING STOCK
225 FATHOMS		2 ¹ / ₁₆	STUDLINK CHAIN CABLE (1 ¹ / ₄ TAYCO FITTED)
90		4 ³ / ₄	STEEL WIRE ROPE
120		5	STREAM TOWLINE
2 @ 90		2 ³ / ₄	HAWERS
2 @ 90		2 ¹ / ₂	WARPS



Charles Connell & Co L^d

N^o 43H

"Empire Mallory"
→ "N"
m Banger Bay
Midship Section
(as built)

"JAS SHANTI"

GLASGOW REPORT No. 64315

Sister vessel to
Empire Glen
Rpt No 64315



© 2020

Lloyd's Register
Foundation

002923-002928-0143