

Lloyd's Register of Shipping.

Ship's Name M.V. "IRISBANK"

Official No. 161861

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

ALTERATIONS:- New accommodation for gunners in No. 4 Shelter 'Tween Deck (p.s)

COMPANIONWAY - A companionway, strongly built of steel, fitted on shelter deck at after end of deckhouse abreast engine casing (p.s) for access to new accommodation for gunners in No. 4 shelter 'tween deck (p.s), opening 4'8" x 2'0", sill 18", closed by a strong hinged wood door capable of being operated from both sides. ✓

SIDELIGHTS: Sidelights fitted in shell in way of new accommodation for gunners, 10" dia. of strong construction, and fitted with strong hinged deadlights. ✓

VENTILATORS: Additional ventilators now fitted in shelter deck to ventilate new accommodation for gunners as follows -

6, 6" dia. cowl ventilators, coamings 30" x .30	} wood plugs and canvas covers provided. ✓
4, 9" " " " " 30" x .32	

SANITARY DISCHARGES: From W.C.s and washbasins in new accommodation in No. 4 shelter 'tween deck, led overboard and fitted with double automatic non-return valves in accessible positions. ✓

Geo. Cockburn

Glasgow. 18th April, 1944

A copy of the above has been attached to the copy of Loadline Report on board the vessel. ✓

Geo. Cockburn

Glasgow. 18th April, 1944

Noted.
J.P.S.
18 APR 1944