

Messrs. Workman Clark's Yard No. 510.

Rule Dimensions:- 425' x 57' x 38.5' to upper deck
29.75' to second deck.

Plans for this vessel were approved on the 31st December last.

A letter has now been received from the Builders to the effect that they propose to increase the moulded depth to the second deck by one inch, and they desire to be informed as to whether this will involve any modification to the scantlings already approved, and that a freeboard suitable for the desired draught of 26 feet will be obtained.

It is submitted the Builders be informed that the scantlings as already approved will be in order for the increased depth, provided the wing brackets be increased by two inches.

It is further submitted the Builders be informed that if the depth to second deck be increased by one inch as proposed, the freeboards intimated in the Secretary's letter of the 31st December 1928 will not be affected, provided the remaining particulars be unaltered.

The draught previously obtained will therefore be increased one inch.



28. 2. 29.



© 2020

Lloyd's Register
Foundation

002938-002946-0095