

35086

## Lloyd's Register of Shipping.

Ship's Name <sup>CAMBRIDGE</sup> ~~lx~~ SUSSEX

Official No. 165389

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in 1937

- 1) Tonnage opening on the shelter deck permanently closed by fitting a B.A. beam, wood decking caulked and payed. ✓
- 2) Wash ports in the tonnage space permanently closed by riveting plates over the openings. ✓
- 3) Several overboard scuppers from the shelter tween decks permanently closed by welding plates over the openings at the shell (3 port and 3 star.) ✓
- 4) Shelter tween deck bulkheads on frames No. 99 star, 98 port, 78 port and star. have been made reasonably watertight by fitting bolted plates over the openings with  $\frac{3}{4}$ " dia bolts spaced  $4\frac{1}{2}$ " apart, jointed with tanned felt. ✓
- 5) The present battening arrangements of the shelter tween deck hatchways are being maintained and are efficient. ✓

Arthur H. Smith  
13/11/39

A copy of the above memorandum has been placed on board the ship.

New gross Tonnage = 13646.50  
" nett " 8272.95

The gross Tonnage on loadline certificate has been amended in accordance with the above.

No alterations have been made to the openings in the tonnage space bulkheads.

See £ 3-3-0 (of 15 NOV 1939)

Noted 2020  
17 NOV 1939  
Lloyd's Register  
Foundation