

Lloyd's Register of Shipping.

Ship's Name ^{CAMBRIDGE} ~~LA~~ SUSSEX

Official No. 165389

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in 11/1939

The shelter tween deck space has been taken off the tonnage and the following alterations have been effected at this time. The beam and wood decking have been removed from the tonnage opening in the shelter deck and wood hatch covers have been fitted with temporary means of closing. The freeing ports in the tonnage well have been opened. The plates at the shell closing the overboard scuppers from the shelter tween deck spaces have been removed. The plates at frames nos 78 p. + s., 98 p. + 99 s. in the shelter tween deck bulkheads have been fitted with hook bolts spaced not less than 12" apart, in place of the close spaced bolts and nuts. The loadline certificate and certified copy have been amended in respect of the new tonnage.

Gross Tonnage = 11063

U. deck " = 10026

Net " = 6516

Arthur H. Smith

27/5/40

A copy of the above memorandum has been placed on board the ship.

Walter
2/6/40

L 4-0-0 (a/c 6 JUN 1940)