

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Date of writing Report

19

When handed in at Local Office

21 SEP. 1928

Port of

SUNDERLAND.

Received at London Office

8261 d 35 22

SEP 22

1928

No. in Survey held at

SUNDERLAND.

Date, First Survey

5th June

Last Survey

8th Aug 1928.

Reg. Book.

90103 on the S.S. 'FAIR WATER'

(Number of Visits 10)

Tons { Gross 4108.
Net 2605.

Built at Sunderland

By whom built

R. Thompson & Co

Yard No. 331

When built 1928

Owners Messrs. The Fairwater Shipping Co.

Port belonging to

Cardiff

Electric Light Installation fitted by

Messrs. Claude Chapman & Co

Contract No. 331

When fitted 1928

System of Distribution

Double wire system

Pressure of supply for Lighting

110

volts, Heating

-

volts, Power

-

volts.

Direct or Alternating Current, Lighting

Direct

Power

-

If alternating current system, state frequency of periods per second

-

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off

Yes

Generators, do they comply with the requirements regarding rating

Yes

, are they compound wound

Yes

are they over compounded 5 per cent.

Yes

, if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel

-

, is an adjustable regulating resistance fitted in

series with each shunt field

Yes

Are all terminals accessible, clearly marked, and furnished with sockets

Yes

, are they so spaced or shielded that they cannot be accidentally earthed,

short circuited, or touched

Yes

Are the lubricating arrangements of the generators as per Rule

Yes

Position of Generators

Engine Room starboard side

is the ventilation in way of the generators satisfactory

Yes

, are they clear of all inflammable material

Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

-

-

, are the generators protected from mechanical injury and damage from water, steam or oil

Yes

are their axes of rotation fore and aft

Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed

Yes

are the prime movers and

their respective generators in metallic contact

Yes

Main Switch Boards, where placed

Engine Room starboard side near dynamo

If the generators and main switchboard are not placed in the same compartment, is each generator provided with

a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

Yes

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes

Yes

are they protected from mechanical injury and damage from water, steam or oil

Yes

, if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards

-

-

are they constructed wholly of durable, non-ignitable non-absorbent materials

Yes

, is all insulation of high dielectric strength and of

permanently high insulation resistance

Yes

, if semi-insulating material is used, are all conducting parts insulated from the slab

with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework

Yes

and is the frame effectively earthed

Yes

Are the fittings as per Rule regarding:— spacing or shielding of live parts

Yes

, accessibility of all parts

Yes

, absence of fuses on back of board

Yes

, proportion of omnibus

bars

Yes

, individual fuses to voltmeter, pilot or earth lamp

Yes

, connections of switches

Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Double pole switches & fuses in dynamo mains, single pole switches & double pole fuses in each outgoing circuit

Instruments on main switchboard

One

ammeters

One

voltmeters

synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Earth lamps

coupled to each through switches & fuses

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules

Yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule

Yes



© 2020

Lloyd's Register
Foundation

002989-002996-0018 1/2

Cables: Single, twin, concentric, or multicore single are the cables insulated and protected as per Tables IV of the Rules Yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 2.5 Kilo

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets Yes

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes

Support and Protection of Cables, state how the cables are supported and protected Lead Armoured in Engine room, Lead Covered in Cabin etc, Armoured Braided in Cargo spaces clipped to underside of deck

If cables are run in wood casings, are the casings and caps secured by screws, are the cap screws of brass, are the cables run in separate grooves. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII Yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements

Joints in Cables, state if any, and how made, insulated, and protected None made

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes state the material of which the bushes are made Lead

Earthing Connections, state what earthing connections are fitted and their respective sectional areas

are their connections made as per Rule

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes, are the fuses double pole Yes

are the switches and fuses grouped in a position accessible only to the officers on watch Yes

has each navigation lamp an automatic indicator as per Rule Yes

Secondary Batteries, are they constructed and fitted as per Rule

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight Yes

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected

how are the cables led

where are the controlling switches situated

Searchlight Lamps, No. of, whether fixed or portable, are their fittings as per Rule

Arc Lamps, other than searchlight lamps, No. of, are their live parts insulated from the frame or case, are their fittings as per Rule

Motors, are their working parts readily accessible, are the coils self-contained and readily removable for replacement

are the brushes, brush holders, terminals and lubricating arrangements as per Rule, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material

are they protected from mechanical injury and damage from water, steam or oil, are their axes of rotation fore and aft

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type

if not of this type, state distance of the combustible material horizontally or vertically above the motors and

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule

Ships carrying Oil having a Flash Point less than 150 F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN	1.	10.	110	90	360.	Large cylinder steam engine			
AUXILIARY									
EMERGENCY									
ROTARY TRANSFORMER									
LIGHTING AND HEATING CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
1.	MAIN GENERATOR...	2	.07592	19	.072	90	30	Pure rubber	Lead covered
	EQUALISER CONNECTIONS								
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER...								
	AUXILIARY SWITCHBOARDS								
2.	ENGINE ROOM	2	.00701	7	.036	13.7	60	"	Lead armoured
	BOILER ROOM								
	ACCOMMODATION								
3.	Salon & Steward	2	.01046	7	.044	19.5	190	"	Armoured Braided
4.	Engineers	2	.01046	7	.044	9.3	120	"	Armoured Braided
5.	WIRELESS	2	.00701	7	.036	15	200	"	Armoured Braided
6.	SEARCHLIGHT	2	.00152	1	.044	.9	240	"	Insulin tubes
7.	MASTHEAD LIGHT...	2	.00152	1	.044	.9	20	"	Lead covered
8.	SIDE LIGHTS...	2	.00152	1	.044	.5	12	"	"
9.	POOP LIGHTS	2	.00152	1	.044	.9	260	"	Armoured Braided
10.	CARGO LIGHTS	2	.00455	16	.38	3	150	"	Braided & Compounded
	ARC LAMPS								
	HEATERS								
MOTOR CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	(a) MOTOR GENERATOR...								
	(b) MAIN MOTOR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
The foregoing is a correct description.

For Clarke, Chapman & Co., Ltd.

Electrical Engineers.

Date

Sept. 17. 1928

Director.

COMPASSES.

Distance between electric generators or motors and standard compass 96 ft.

Distance between electric generators or motors and steering compass 90 "

The nearest cables to the compasses are as follows:

A cable carrying 5 Ampères 12 feet from standard compass 6 feet from steering compass.

A cable carrying 5 Ampères 6 feet from standard compass 12 feet from steering compass.

A cable carrying 0 Ampères 0 feet from standard compass 0 feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power? Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted? Yes

The maximum deviation due to electric currents was found to be 0 degrees on 0 course in the case of the standard compass, and 0 degrees on 0 course in the case of the steering compass.

Builder's Signature.

Date Sept. 19. 1928

Is this installation a duplicate of a previous case? No. If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c.)

The above installation is in accordance with the Society's Rules. The vessel is eligible in my opinion for notation as light vessel.

It is submitted that this vessel is eligible for THE RECORD. Elec. Light.

26/10/28

Total Capacity of Generators 10 Kilowatts.

The amount of Fee ... £ 10 : : 3 Aug 19.28

Travelling Expenses (if any) £ : : 18 Aug 19.28

W.T. Badger

Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

Elec. Light



© 2020

Lloyd's Register Foundation