

Lloyd's Register of Shipping.

2992

Ship's Name S. S. Farnwater

Official No. 148300

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in Dec. 1945.

Forecastle blshd: 5' x 4' tonnage opening fitted at centre with 18 coamings. Closed by 3½" weather boards in free height riveted channels.

Poop blshd: openings closed up.

Companions: the companion on fo'c'sle deck removed & opening plated over.

An entrance house has been built on the poop deck giving access to crew's quarters. Opening 4'-10" x 22½ (PoS)

Steel 19" closing hinged teak door - operating either side.

Gangways: the gangway from bridge to fo'c'sle deck has been removed & a life line fitted on fore deck.

Hatches: the cargo hatch on poop deck has been removed & the opening plated over.

A small hatch 1'8" x 27" has been fitted on the after end of the poop deck. Coaming 6" x 3" x .35" F.E.W. to deck.

Closing boated 10 ft. cover.

Ventilators: 5 vents have been removed from the forecastle deck & the openings plated over.

New vents have been fitted on the poop deck as follows:-

12 @ 6" dia. Coamings 36" x .36" 2 @ 9" dia. Coamings 36" x .30"

Closing wood plugs & canvas covers.

The first certificate & copy have been amended as necessary.

The port of registry was amended at Newcastle.

P. D. Groudaue

Sunderland 5.11.46.

A copy of the above has been placed on board.

West
J.W.
S. November