

AT. COPY.

Rpt. C.11 (Comp.).

CLAN CUMMING 35463  
CLAN CHATTAN 35258  
CLAN BUCHANAN 35519  
CLAN CAMERON 34825  
CLAN FRASER 35881

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

Index. No.

35823

(For London Office only).

Ship's Name <b>"CLAN FORBES"</b>	Official Number <b>165951</b>	Nationality and Port of Registry <b>British Glasgow.</b>	Gross Tonnage <b>7529</b>	Date of Build <b>1938</b>	Port of Survey <b>Glasgow</b>
Moulded Dimensions: Length <b>157'</b> Breadth <b>62.75'</b> Depth <b>32.51'</b>					Date of Survey <b>While Building</b>
Moulded displacement at moulded draught = 85 per cent. of moulded depth <b>15507</b> tons					Surveyor's Signature <b>N.L. Swinton.</b>
Coefficient of fineness for use with Tables <b>.685.</b>					Particulars of Classification <b>+ 100A1. With Freeboard (Contemplated)</b>

<b>Depth for Freeboard (D).</b> Moulded depth ... <b>32.51'</b> Stringer plate ... <b>.04'</b> Sheathing on exposed deck $T \left( \frac{L-S}{L} \right) =$ <b>✓</b> Depth for Freeboard (D) = <b>32.55'</b>	<b>Depth correction.</b> (a) Where D is greater than Table depth (D-Table depth) R = <b>(32.55-30.47) 3 = +6.24"</b> (b) Where D is less than Table depth (if allowed) (Table depth-D) R = <b>✓</b> If restricted by superstructures <b>✓</b>	<b>Round of Beam correction.</b> Moulded Breadth (B) <b>62.75'</b> Standard Round of Beam = $\frac{B \times 12}{50} =$ <b>15.06</b> Ship's Round of Beam <b>15.50</b> Difference <b>Excess .44</b> Restricted to Correction = $\frac{\text{Diff}^2}{4} \times \left( 1 - \frac{S_1}{L} \right) = \frac{.44^2}{4} \times .0055 =$ <b>Nil</b>
---	--	---

## DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)
Poop enclosed ...	33.08'	33.08'	8.2'	✓	33.08'
" overhang ...	.92'	.46'			.46'
R.Q.D. enclosed ...					
" overhang ...					
Bridge enclosed ...					
" overhang aft ...					
" overhang forward ...	418.42'	418.42'	8.2'	✓	418.42'
Forecastle enclosed ...					
" overhang ...					
Trunk aft ...					
" forward ...		DIFF × 1/2			
Tonnage opening aft ...	4.58'	2.52'	8.2'	✓	2.52'
" forward ...					
Total ...	457.00'	454.48'			454.48'

Standard Height of Superstructure **7.50'** ✓  
 " " R.Q.D. **✓**  
 Deduction for complete superstructure **42.00'** ✓  
 Percentage covered  $\frac{S}{L} =$  **100.00.** ✓  
 "  $\frac{S_1}{L} =$  **99.45.** ✓  
 "  $\frac{E}{L} =$  **99.45.** ✓  
 Percentage from Table, Line A. **99.32** ✓  
 (corrected for absence of forecastle (if required))  
 Percentage from Table, Line B. **✓**  
 (corrected for absence of forecastle (if required)) **✓**  
 Interpolation for bridge less than 2L (if required) **✓**  
 Deduction = **42.00 × 99.32 = 41.72.** ✓

## SHEER CORRECTION.

Station	Standard Ordinate	S M	Product	Actual Ordinate	Effective Ordinate	S M	Product
A.P. ...	55.70	1	55.70	60"	68.50	1	68.50
1/2 L from A.P. ...	24.79	4	99.16	27	30.48	4	121.92
3/8 L " ...	6.13	2	12.26	8 1/2	7.53	2	15.06
Amidships ...	-	4	-	-	-	4	-
3/8 L from F.P. ...	12.25	2	24.50	14	14.13	2	28.26
1/2 L " ...	49.57	4	198.28	54	57.18	4	228.72
F.P. ...	111.40	1	111.40	120	128.50	1	128.50
Total ...			501.30	+8 1/2"			590.96

Correction =  $\frac{\text{Difference between sums of products}}{18} \left( .75 - \frac{S}{2L} \right) = \frac{89.66}{18} \times .25 = -1.25"$   
 If limited on account of midship superstructure.

Actual height of superstructure = **8.20'** ✓  
 Standard " " " = **7.50'** ✓  
 Mean actual sheer aft = **Excess.** ✓  
 Mean standard sheer aft = **Excess.** ✓  
 Mean actual sheer forward = **Excess.** ✓  
 Mean standard sheer forward = **Excess.** ✓  
 Length of enclosed superstructure forward of amidships = **6.1.1.1.** ✓  
 " " aft of " = **6.1.1.1.** ✓

## Deduction for Tropical Freeboard.

## Addition for Winter and Winter North Atlantic Freeboard.

Depth to Freeboard Deck = **32.55'** ✓  
 Summer freeboard = **4.40'** ✓  
 Moulded draught (d) = **28.15'** ✓

## Deduction for Tropical freeboard and addition for

Winter freeboard =  $\frac{d}{4}$  inches = **7.04 = 7"** ✓

Addition for Winter North Atlantic Freeboard (if required) = **✓**

## Deduction for Fresh Water.

Displacement in salt water at summer load water line  
 $\Delta =$  **15804 e 28.0** } **16057** ✓  
 $\Delta =$  **16470 e 29.0** }  
 Tons per inch immersion at summer load water line  
 $T =$  **55.35 e 28.0** } **55.50** ✓  
 $T =$  **55.75 e 29.0** }  
 Deduction =  $\frac{\Delta}{40T}$  inches  
 $=$  **7.23** ✓  
 $=$  **7 1/4"** ✓

## TABULAR FREEBOARD corrected for Flush Deck (if required)

Correction for coefficient  $\frac{6.85 + .68}{1.36} = \frac{1.365}{1.36}$  ✓

Depth Correction ... **6.24** ✓  
 Deduction for superstructures ... **41.72** ✓  
 Sheer correction ... **1.25** ✓  
 Round of Beam correction ... **-**  
 Correction for Thickness of Deck amidships ... **-**  
 Other corrections, scantlings, etc. ... **-**

+	-
6.24	-
-	41.72
-	1.25
-	-
-	-
-	-
6.24	42.97
Summer Freeboard = <b>52.87</b>	

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, ~~Wood~~ Steel, Deck: -

Tropical Fresh Water Line above Centre of Disc **14 1/4"** ✓  
 Fresh Water Line " " **7 1/4"** ✓  
 Tropical Line " " **7"** ✓  
 Winter Line below " " **7"** ✓  
 Winter North Atlantic Line " " **✓**

Tropical Fresh Water Freeboard ... **3' 2 1/2"** ✓  
 Fresh Water " " **3' 9 1/2"** ✓  
 Tropical " " **3' 9 3/4"** ✓  
 Winter " " **4' 1 1/4"** ✓  
 Winter North Atlantic " " **✓**

4' 4 3/4"  
 3' 2 1/2"  
 3' 9 1/2"  
 3' 9 3/4"  
 4' 1 1/4"  
 Lloyd's Register  
 RECEIVED



8

A new form should be prepared if any alterations that affect the freeboard have been made. If no such alterations have been made, the Surveyor should endorse the form on this side with his signature and the date.

Trade of ship *International.*

Names of sister ships *'Clan Cameron', 'Clan Chattan', 'Clan Cumming', 'Clan Buchanan' (with Modification)*

Builder's name and yard number *The Greenock Dockyard Co. Ltd., W. 434.*

Owners *The Clan Line Steamers, Ltd.*

Fee £ *18* — —

*Clan Forbes.*



© 2021

Lloyd's Register  
Foundation