

29 JAN 1944

Glasgow Rpt No 72458^A

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name

"CALGARY"

Official No.

143707

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Conversion to Oil Fuel.New air pipes fitted.Forecastle Deck :-

1 at 4" dia. air pipe (36" high) fitted (p+s) to No 1 D.B. tank ✓

Bridge Deck :-

2 at 4" dia. air pipes (36" high) fitted (p+s) to No 2 D.B. tank. ✓

2 " 4" " " (36" ") " (") " No 4 " " ✓

1 " 4" " " (36" ") " (") " Overflow " ✓

1 " 4" " " (36" ") " (") " Settling " ✓

Upper Deck :-

1 at 4" dia. air pipe (36" high) fitted (p+s) to No 7 D.B. tank. ✓

All above air pipes are strongly constructed and are fitted with gauges. ✓

Existing air pipes to Nos 1, 3, 7 and 8 D.B. tanks have now been fitted with gauges. ✓

Appliances for closing access openings in bulkheads at ends of detached superstructures. :-

Poops :- Sluice boards with rivetted channels now dispensed with and 2 hinged hardwood doors fitted. Doors 2" thick, sill 18" and doors are capable of being operated from both sides. ✓

New Sidelights :-

14 at 12" dia. with deadlights to Poop accommodation. ✓

1 at 12" " " " Carpenter's store. ✓

New Ventilators now fitted to Accommodation :-Forecastle Deck :- 4 at 8" dia. cowl ventilators (36" x 3/8" coaming) ✓

1 at 5" " goose neck. (36" high) ✓

Bridge Deck :- 1 at 6" dia. cowl ventilator (36" x 3/8" coaming) ✓Poop Deck :- 2 at 12" " " (36" x 3/8" ") ✓

4 " 8" " " (30" x 3/8" ") ✓

2 " 6" " mushroom Ventilators. Vents fitted with screw down heads. ✓

1 " 15" dia. cowl ventilator (30" x 3/8" coaming) to tunnel. ✓

Wood plugs and canvas covers supplied ✓

A copy of this report has been placed on board the vessel. ✓

James Fleming. Glasgow. 31st December 1944.