

3 JUL 1956

10 JUL 1956 62312.  
Index No. (For London Office use)

# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name s.s. "CALGARY" Official No. 143707

Port of Registry LIVERPOOL.

This ship has been under survey at HULL.

on 29th June 1956 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:-

Eight open overboard scuppers (4p & 4s) draining bridge tween decks now blanked off at shell with welded steel plates and the tubes filled with cement. ✓

Two (1p & 1s) 4 inch diameter scupper pipes now fitted in upper deck within bridge for draining bridge tween decks. Both pipes led to engine room bilges, their lower ends being in easily accessible positions and fitted with self-closing, weighted lever cocks. ✓ Intermediate bulkheads in bridge fitted with drain holes at wings. ✓

*T.F. Naisby*

T.F. NAISBY

29th June 1956.

Hull.

*J.P.P.*  
*16-7-56.*

A copy of this Report has been placed on board.



© 2021

Lloyd's Register Foundation

003006-003012-0229