

9-AUG 1954

Rpt. C. 11 (Contd.)

Index No.

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name "CANBERRA" ex "Admiral Fraser" Official No. 182979.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Alterations:-

A 24" dia x 1.10" thick Samson Post ventilator fitted (ps) in way of Bridge front.
Upper & lower deck plating efficiently doubled & posts stayed to bridge front.

^{3rd.}
Lower deck erected between Nos 2/5 tween decks, tonnage openings fitted.
Openings 4'-6" x 3'-0". - portable plate with hook bolts.

Cockhouse amidships entrance rearranged.

Additional door fitted (ps) opening 5'-0" x 23". 24" coaming. 2" wood door. ^{operated both} sides.

Wood door (ss) at forward end repositioned outboard.

Existing W.T. door (ss) repositioned 6'-0" aft. opening 5'-0" x 2'-6".

New access opening to tween deck stores (ss). Opening 3'-6" x 3'-0".

" " " " " (ps). " 4'-9" x 27"

Deck plating in way of openings efficiently doubled.

Original access opening to tween deck stores (ss) plated over.

To Plans Room

Have you any
comments to
make about

Derrick post?

No

James Fleming
Glasgow

7/8/54.

Noted

AK

98.54



© 2020

Lloyd's Register
Foundation