

9-AUG 1954

Rpt. C. 11 (Contd.)

Index No.

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name "CANBERRA" of "Admiral Fraser"

Official No. 182879.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Alterations:-

A 24" dia x 1.10" thick Samson Peak ventilator fitted (ps) in way of bridge front.
Upper & lower deck plating efficiently doubled & posts stayed to bridge front.

^{Shd.}
Lower deck plating between Nos 4/5 lower decks, tonnage openings fitted.
Openings 14'-6" x 3'-0". - portable plate with hook bolts.

Deckhead amidships entrance rearranged.

Additional door fitted (ps) opening 5'-0" x 23". 24" coaming. 2" wood door. ^{spun out with} sides.

Wood door (ss) at forward end repositioned outboard.

Existing W.T. door (ss) repositioned 6'-0" aft. opening 5'-0" x 2'-6".

New access opening to lower deck stores (ss). Opening 3'-6" x 3'-0".

" " " " " (ps). " 4'-9" x 27"

Deck plating in way of openings efficiently doubled.

Original access opening to lower deck stores (ss) plated over.

To Plans Room

Have you any

comments to

make about

Derrick post?

No

AM

10-8-54

James Fleming
Seagoing

7/8/54.

Noted

FR

98-54



© 2020

Lloyd's Register
Foundation