

# Lloyd's Register of Shipping.

Ship's Name S.S. CAPE DREPANON

Official No. ....

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in .....

## ALTERATION TO NO 3 HOLD AND CROSS BUNKER

- 1] The transverse bulkheads between No 3 hold and Cross Bunker and between No 3 tween decks and Cross Bunker tween decks now removed.
- 2] The existing hatchways on Second Deck to No 3 hold and Cross Bunker now combined to form a new hatchway having dimensions 27'-6" x 20'-0"
- 3] The existing hatchways on Upper Deck to No 3 and Cross Bunker tween decks now combined to form a new hatchway, having dimensions 23'-11 1/4" x 20'-0"

One additional hatch beam, of all welded construction, now fitted in the new upper deck hatchway. 18 1/4" deep at  $\pm$  tapered to 10 1/2" deep at sides. Web .50 thick with 8" x 7 1/2" face plate.

Hatch side coaming supported by two C.A. stays (p.s.s.)

New hatchway provided with two tarpaulins, cleats, battening bars and locking bars and wedges in accordance with Rule Requirements.

*J. Macdonald*

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING  
CORK.

167 JANUARY 1961.



Noted.

In accordance with approved plans.

*James*  
17/1/61