

T.S.S. No 438
EQUIPMENT NUMISER

23 MAY 1938


Approved
23 MAY 1938

HULL	$\frac{457 \times 62.75 \times 32.51 \times .685}{100}$	= 6386.12
TUNDRY	$\frac{457 \times 62.25 \times 8.21 \times .75}{150}$	= 1166.00
POOP	$\frac{30.58 \times 47 \times 8 \times .75}{200}$	= 43.05
ENGINE BRIDGE	$\frac{101.42 \times 60.87 \times 8 \times .75}{200}$	= 185.00
FCSIF	64.66×43.05	= 420
SAIDON HOUSE	$\frac{24.84 \times 60.87 \times 8.5 \times .75}{250}$	= 38.50
ENGERS HOUSE	$\frac{81.37 \times 52.54 \times 8 \times .75}{250}$	= 102.62
OFFICERS HOUSE	$\frac{48 \times 18.1 \times 8 \times .75}{250}$	= 20.81

EQUIPMENT No 8026.38


grade 7850

2 BOWER ANCHORS - EACH	7 1/4 cwt (ex stock)	90
1 " " "	6 " " "	76 cwt
1 STREAM	25 3/4 " " "	
330 FTHMS 2 3/8" TAYCO STUD LINK CABLE		
(ROLE 2 3/8" DIA 300 FTHMS)	Owners extra 30 fthms	
120 FTHMS 4 3/4" 6/27 STEEL WIRE STREAM		
130 " 5 1/2" 6/27 " " "		
4 WARPS EACH 90 FTHMS 8" MANILA (220 lbs test per yarn)		
4 WARPS 90 " 7" " "		
4 @ 90 FTHMS 3 1/2" 6/24 WIRE ROPE		



29 MAY 1938

EQUIPMENT Nos



© 2021

Lloyd's Register
Foundation

B.C.