

Kaiser Co. Inc. Portland Org.

T2 - SE-A1 Type tanker

to Chief Surveyors.....

Received from Chief Surveyors.....

SEL'S NAME <sup>GB</sup> S.S. "THEODOXUS" ex. "MODOC POINT" REPORT Gal. No. 5030

For the CHIEF SHIP SURVEYOR and CHIEF ENGINEER SURVEYOR.

In cases which have to be submitted to the Classing Committee "the endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case so that the Classing Committee may have all the salient points presented in the endorsement."— (Extract from Sub-Committee's Report, 24/5/92.)

of Survey S.S. for Classification and When due Repairs

This Tanker was built in 1945 and classed with the American Bureau of Shipping.

Classification with this Society is desired.

Plans for this type of vessel have been examined in this Office, and the scantlings and arrangements found suitable for the class 100A- "Carrying Petroleum in Bulk".

The GALVESTON Surveyor in a First Entry Report and Rpt.8, reports (9.48), the vessel examined in dry dock and afloat, the scantlings and arrangements verified, and the requirements for Vessels Not Built Under Survey. and of a Periodical Special Survey complied with.

The cutting and strapping of the deck, and shell carried out at this time.

Permanent repairs effected to shell plate No.7 in 1st strake below sheer (s.s.), and the Surveyor recommends this item be deleted from a Condition of Class.

Repairs effected to a number of fractures in bulkheads, and tee bars fitted to the bulkhead brackets in way.

"Subject to 30 fathoms of chain cable being supplied at the first opportunity"

100A1 "Carrying Petroleum in bulk". "Fitted for oil Fuel F.P. above 150 F" 9.48 Gal.  
S.S. Gal. 9.48  
Classed 9.48  
*See Mch. endorsement.*

1 Dk. 2nd Dk in way of Mch space. "Elec.welded" "Longitudinal Framing". Cell D.B. UE. 82'. 238t. DTf 32'. 759t. F.P.T. 314t. A.P.T. 60t.

F.K. 14 BH.  
P 108'. B 36'. F.56'.

Mch aft.  
O.L. 523.5'


E.S.D.  
2 5/16"



Equipment letter for fees g f in red

C.S.S. Records Dept.

to note. Fractures at Bhd.



© 2020

Lloyd's Register Foundation  
7/12/48

003092-003099-0013