

(Electric Light Report)

M.V. "SILVERELM" - Sunderland Report No. 28808.

(Sunderland Forge & Engineering Co., Ltd.)

Extract from letter (dated 30. 9. 25) from Mr. Badger (Nwc)
to Mr. Carnaghan. re M.V. "SILVERCEDAR"

(This installation is a duplicate of s.s. "SILVERCEDAR")

Lead covered, armoured and braided cables used in engine room for main cables and engine room lighting. From top of engine room to forward and aft the mains are V.I.R. braided cables run in galvanised steel conduit, the conduit being taken along (on top) upper deck and round hatch coamings, watertight junction boxes being fitted in convenient places for drawing in the cable and for inspection. All mains were 2500 meg grade.



© 2020

Lloyd's Register

005100-005105-0057
Foundation