

23 JAN 1946

Rpt. G. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "SILVERBELL".

Official No. 147648.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Vessel has now reverted to pre-war freeboard assignments.

- NOW DONE. (1) Tonnage opening in shelter deck restored and fitted with efficient temporary covers. /
- (2) 5" diameter overboard scupper with automatic screwdown non-return valve controlled from shelter deck fitted in tonnage well port and starboard. /
- (3) After tonnage bulkhead no openings. /
Forward tonnage bulkhead opening (p & s) fitted with 3" shifting boards in channels as originally. /
- (4) Scupper pipes in shelter tween decks where led to hold bilges blanked off at deck level and where led to machinery bilges lever weighted cocks fitted. /
- (5) Tween deck hatchways and closing appliances etc., are in order. /
- (6) Freeboards now marked from upper deck. /

W. Henderson
SURVEYOR TO LLOYD'S REGISTER.

Liverpool 15. 1. 46

AR
14.1.46

