

GLASS CONTEMPLATED.

G.R. 130.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) --- G.Z.D.W

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
164,965.		Cape Palliser.		78/1936. Hull.	
No., Date, and Port of Previous Registry (if any). ---					
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Single Screw.	Selby	1936	Cochrane & Sons Limited Selby	
Number of Decks .. One & Raised quarter		Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ..		Feet.	Tenths.
Number of Masts .. Two		Length at quarter of depth from top of weather deck at side amidships to bottom of keel ..		169	7
Rigged .. Ketch		Main breadth to outside of plank ..		27	6.5
Stern .. Cruiser		Depth in hold from tonnage deck to ceiling at midships ..		14	2
Build .. Clencher		Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ..			
Galleries .. None		Depth from top of beam amidships to top of keel ..			
Head .. Straight Stem		Depth from top of deck at side amidships to bottom of keel ..			
Framework and description of Steel Trawler vessel ..		Round of beam ..		35	7
Number of Bulkheads .. Five		Length of engine room, if any ..			8
Number of water ballast tanks, and their capacity in tons .. None.					

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel .. Tons. Ditto per inch immersion at same depth .. Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
One	Reciprocating Steam Triple Expansion Direct Acting Inverted Cylinder	Engines. British	Engines. 1936	Engines. Charles D. Holmes & Co., Ltd., Hull	Three 14 1/2"	27"		N.H.P. 132
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.				
	Description Cylindrical				24"			I.H.P. 850
	Number One Multitubular							
	Iron or Steel Steel	British	1936	Charles D. Holmes & Co., Ltd., Hull.	40"			12 Knots.
One	Loaded Pressure 220 lbs.							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ..	430.00	On account of space required for propelling power	229.02
Space or spaces between Decks ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk ..			
Forecastle (Side Houses) ..	4.79		
Bridge space ..		These spaces are the following, viz. :-	
Poop or Break ..	22.90	Below deck forward & aft	
Side Houses ..		Round House Aft, Side House in Forecastle	
Deck Houses ..	18.23	(Number of Seamen or Apprentices for whom accommodation is certified...22.....).	55.26
Chart House ..			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ..	18.80	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-	
Excess of Hatchways ..			
		Cubic Metres.	
Gross Tonnage ..	494.72	Masters accommodation 6.33	20.16
Deductions, as per Contra ..	304.44	Chart Space 4.05	
Register Tonnage ..	190.28	Wireless Telegraphy Space 2.77	
		Boatswain's Store 7.01	
		Total ..	304.44

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 118.27 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 19.06 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle - Length 25.05' = 15.51 Tons.

Name of Master	Certificate of	Service Competency	No. No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
Hudson Steam Fishing Company Limited St. Andrews Dock, Kingston-upon-Hull.			
Sixty-four (64) shares.			
Archibald Hudson of St. Catherines, Swanland Road, Hessle, E. Yorks. - Manager.			
Dated 13th October 1936.			