

DIMENSIONS - 425'-0" x 57'-0" x 38'-7" ML⁰ TO UPPER DK.

NUMERALS:

$L \times D$	425×37.83	=	16077.75
$L \times (B+D)$	$425 \times (57 + 37.83)$	=	40302.75
L/D	$425 \div 37.83$	=	11.02
D		=	37.83
d		=	26.08

EQUIPMENT NUMERAL

$$\begin{array}{r} L \times (B+D) \quad 425 \times (57+38.58) = 40621 \\ \text{Houses} \quad 75 \times 8 \times .5 = 300 \\ \hline 40921 \end{array}$$

Grade 6+

BA. SECTIONS N.B.S



EQUIPMENT:

RIVETING:

TANK TOP PLATING. (ceiled in way of Hatches)

CENTRE STRAKE ~~54~~" x .52 To .44"
REMAINDER .46 To .42" .54" IN MOTOR ROOM.
MARGIN PLATE 41" x .56" .54 @ 27" SPACING.

FRAMING:

DOUBLE BOTTOM

BRACKET FLOORS

Harland & Wolff'
No ~~972~~ 984

m/s Ernebank

Midship Section
as built

RETAIN



© 2020

Lloyd's Register
Foundation

003175-003180-0095