

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "GREEN RANGER" Official No. 184317

Port of Registry London.

This ship has been under survey at Immingham.

on 17th August, 1954 and subsequently, / and the following alterations to the conditions of

assignment of loadlines have now been effected/~~found~~

Wing Ballast Tanks forward (p.& s.) converted to carriage of petroleum and on this account 3" dia. air vents (1 p.& s.) led into existing 4" dia. main from central petroleum tanks, valve controlled and led up mast. ✓

New cofferdam for above - frs.35/36 (p.& s.) fitted with 2" dia. gooseneck ventilators 24" x .30" coaming and fitted with gauze covers on focsle deck. ✓

Additional ventilators fitted on focsle deck (s.s.a.) on account of new gas-tight compressor compartment in focsle (s.s.).

1 - 9" dia. mushroom ventilator, coaming 36" x 3/8" with canvas cover ✓

1 - 9" dia. cowl ventilator, coaming 36" x 3/8" with wood plug and canvas cover. ✓

Hatch fitted on focsle deck to compressor room, size 1'-9" x 1'-9", coaming 24" x 3/8". Fitted with hinged steel cover with rubber packing secured by 6 toggles. ✓

Emergency Fire Pump fitted in No.1 Hold (p.s.a.) and access hatch now fitted over on upper deck in focsle. ✓

Size of hatch 1'-10" x 1'-10" with coaming 18" x 3/8" and fitted with hinged steel cover with rubber packing, secured by 6 toggles. ✓

1 - 9" Cowl vent focsle deck (port) coaming 36" x 3/8" to Emergency Fire Pump compartment. ✓

Wood plug and canvas cover provided. ✓

Harold Turner

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING. GRIMSBY.

24th August, 1954.

J.H.H.
25 AUG 1954

A copy of this Report has been placed on board.