

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.  
Lloyd's Register.

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.  
Signal Letters (if any) G.Y.Q.Z.

Official Number.	Name of Ship.	No., Date, and Port of Registry.			
164,018.	Lady Philomena.	10/1936 Hull.			
No., Date, and Port of Previous Registry (if any). -----					
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam S/Screw.	Beverley	1936	Cook Welton & Gemmell Limited, Beverley.	
Number of Decks <u>One &amp; Raised Qr. Deck</u>		Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post .. .. .		Feet.	Tenths.
Number of Masts <u>Two</u>		Length at quarter of depth from top of weather deck at side amidships to bottom of keel .. .. .		155	7.5
Rigged <u>Ketch</u>		Main breadth to outside of plank .. .. .		26	1.5
Stern <u>Cruiser</u>		Depth in hold from tonnage deck to ceiling at midships.. ..		14	1.5
Build <u>Clencher</u>		Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards.. .. .			
Galleries <u>None</u>		Depth from top of beam amidships to top of keel .. .. .			
Head <u>Straight Stem</u>		Depth from top of deck at side amidships to bottom of keel ..			
Framework and description of <u>Steel Trawler</u> vessel .. .. .		Round of beam .. .. .		32	6.7
Number of Bulkheads <u>Five</u>		Length of engine room, if any .. .. .			5
Number of water ballast tanks, and their capacity in tons <u>None.</u>					

## PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ----- Tons. Ditto per inch immersion at same depth ----- Tons.

## PARTICULARS OF PROPELLING ENGINES, &amp;c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
One	Triple Expansion Direct Acting Inverted Cylinder	Engines. British	Engines. 1936	Engines. Chas. D. Holmes & Co., Ltd., Hull.	Three	13 1/2"	26"	N. H. P. 105
No. of Shafts.	Particulars of Boilers.							
	Description <u>Cylindrical Multitubular</u>	Boilers.	Boilers.	Boilers.				
One	Number <u>One</u>				23"			I. H. P. 640
	Iron or Steel <u>Steel</u>	British	1936	Chas. D. Holmes & Co., Ltd., Hull.	37"			12 Knots.
	Loaded Pressure <u>200 lbs.</u>							

## PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck .. .. .	372.36	On account of space required for propelling power	191.94
Space or spaces between Decks.. ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk .. .. .		These spaces are the following, viz:— <u>Below Dk. forward</u> <u>---do--- Aft.</u> (Number of Seamen or Apprentices for whom accommodation is certified...16.....).	51.18
Forecastle .. .. .	20.63	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Bridge space .. .. .	10.51	Master's Accommodation 6.54 )	
Deck Houses.. .. .		Wireless Telegraphy Space 1.93 )	
Side Houses.. .. .		Boatswain's Store 8.34 )	
Chart House .. .. .	13.64		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 .. .. .			
Excess of Hatchways .. .. .			
Gross Tonnage .. .. .	417.14	Cubic Metres.	
Deductions, as per Contra.. .. .	259.93	1180.51	
Register Tonnage .. .. .	157.21	735.61	
		444.90	
		Total .. .. .	259.93

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 96.04 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 13.64 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle L.27!75 - 20.36 Tons.

Name of Master	Certificate of	Service No.	Competency No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
Jutland Amalgamated Trawlers Limited St. Andrews Dock, Kingston upon Hull.			
Sixty-four (64) Shares. Dated 4th February 1936.			
Edward Cargill same address—Manager—			

Lloyd's Register  
Foundation