

003208-003216-0100

1,12,22.

BOARD REPORT on the Messrs Swan, Hunter & Wigham Richardsons  
Ship No 1216.

Mld. 475'-0" x 58'-9" x  $\begin{cases} 32'-6" \\ 40'-6" \end{cases}$

- ① As a full scantling ship with moulded depth of 40'-6" to the upper deck, with bridge assumed to be closed, and 80% excess sheer; the summer moulded draught =  $30'-11\frac{1}{4}"$
- ② As a full scantling ship with moulded depth of 40'-6" to the upper deck with flush deck and 50% excess sheer, the summer moulded draught =  $30'-5\frac{1}{4}"$
- ③ As a complete superstructure ship with a moulded depth of 32'-6" to 2nd. Deck and 40'-6" to superstructure deck, the summer moulded draught =  $27'-5\frac{1}{4}"$   
Draught desired =  $29'-0"$  med. or extreme

Copy to Mr. Gearing.

W.W. 6-5-25.