

Modified in red to agree with increase in mld. depth by 3"

Index No. 70725 For London Office only.

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.—STEAM SHIPS.

1

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey  
Date of Survey 6-5-25  
Name of Surveyor

Ship's Name <i>Hunter-Wigham Richardson Ltd</i> <i>No 1216 Ship</i>	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification. <i>Full scantling with Bridge.</i>
---	-----------------------------------	------------------	----------------	----------------	--

LENGTH. <i>475'-0"</i>	BREADTH. <i>58'-9"</i> <i>59'-08"</i>	DEPTH. <i>40'-9"</i> <i>37'-21"</i>	UNDER DECK TONNAGE. <i>8500</i>
Length on LOADLINE. <i>475.0</i>	Frame Depth Rule <i>12</i> <i>7 1/2</i> <i>4 1/2</i> <i>No 1216</i> <i>1.33</i>	Ceiling + 20. <i>7 1/2</i> <i>Sheer + 80</i>	Peak <i>Inc.</i> Tanks <i>For 8" x 10" frames</i> <i>- 64</i>
CORRECTED DIMENSIONS. <i>475.0</i>	<i>58.66</i>	<i>38.21</i>	<i>8436</i>

Co-efficient of fineness.....*.793*  
Any modification necessary {  
[Para. 4 (a) to (e)]\*  
Co-efficient as corrected .....*Assumed .77*

Sheer { Stem..... }  
at { Sternpost ... }  
 $\div 2 =$  ...Mean *36/28.75*  
*.80*

Sheer at  $\frac{1}{2}$  of the length from { Stem  
Sternpost }  
 $\div 2 =$  ...Mean

Gradual mean Sheer .....*(50% mean) 86.25*

Standard mean Sheer [Table, Para. 18] .....*57.50* Correction  
Difference.....*28.75*  $\div 4 =$  *- 7.187*

§ If limited as Para. 18 (f) .....*- 7 1/4"*

Rise in Sheer { At front of bridge house..... }  
from amidships { At after end of forecastle ..... }

¶ Fall in Sheer {  
Para. 18 (d) }  
 $\div 2 =$  ✓  
Length uncovered ..... ✓ Correction

ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C.....*(11'-9" - 3'-2 1/2")*

Correction for Length, if required (Para. 12, 13, and 14) .....*8'-6 1/2"*

Freeboard by Table A, corrected for sheer, and for length, if required (Para. 12, 13, and 14) .....*8'-5 1/2"*

Difference .....*10'-11 1/2"*

Percentage as below.....*25.86*

Table A Cor'd for L = *11'-6 3/4"*  
" C " " " *8'-5 1/2"*  
*3 - 1 1/4" x 7.2% = 2.68*  
*7.76*  
*5.08*

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) .....*- 5 1/4"*

Allowance for Deck Erections .....*- 5 1/4"*

Length.	Length allowed.	Height.
Forecastle..... <i>Assumed</i>	<i>59.37</i> ✓	
Bridge House..... <i>Assumed</i>	<i>145.16</i> ✓	
+ Raised Qr. Dk.....		
Poop.....		
Total	<i>204.53</i>	<i>.431</i>
Length of Ship	<i>475.00</i>	
Corresponding percentage { (Para. 11, 12, 13, or 14)	<i>25.86</i> x	

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck:—

Fresh Water Line	above centre of Disc	...
Indian Summer Line	" " "	...
Winter Line	below " "	...
Winter North Atlantic Line	" " "	...

Moulded Depth as measured.....*40'-9"*  
*wd. dk. less str. 3 1/2"*  
*Fitted 3"*  
Addition for Keel below base line for draught record.....*2 1/2* inches.

CORRECTION FOR LENGTH.

Length of Ship on Loadline.....*475.0*

Length in Table .....*488.5*

Difference .....*13.5*

Correction for 10ft., Table A. ....*1.7* Table C. *.8*

x Difference divided by 10 .....*2.295* (if required.) *1.08*

If  $\frac{1}{10}$ ths length covered divide by 2 *- 2 1/4"* ✓ *- 1"* ✓

CORRECTION FOR IRON DECK.

Proportion covered, if less than  $\frac{1}{10}$ ths length covered .....*3 1/2"* *In mld. depth*

Thickness of usual wood deck, less stringer .....*3"* *Teak deck fitted.*

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....

Round of Beam .....*Assumed normal*

Normal round.....

Difference .....  $\div 2 =$  .....

Proportion of Deck uncovered (Para. 19) .....

Freeboard, Table A .....*11'-9"*

Correction for Sheer .....*7 1/4"*

Correction for Length .....*11' - 1 3/4"*

Allowance for Deck Erections .....*2 1/4"*

Correction for Round of Beam.....*10' - 11 1/2"*

Correction for fall in Sheer (if any).....*5"*

Correction for Steel Deck (if required) .....*10' - 6 1/2"* ✓

Additions for non-compliance with provisions of Para. 11 (d) and (e) *For 2 1/2" Sheathing Amidships* *- 1/2"*

Other Corrections (if any) .....*10 - 5 1/2"*

Winter Freeboard .....*10' - 1 1/2"*

Summer Freeboard .....*9' - 10 1/4"*

Indian Summer Freeboard .....*9 - 2 1/2"*

N. A. Winter Freeboard .....*+* *13/4"*

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side.

Winter Freeboard from deck line .....*10' - 7 3/4"*

Summer " " " .....*10' - 0"*

Indian Summer " " " .....*9 - 4 1/4"*

N. A. Winter " " " .....*10' - 0"* *9' - 11 1/2"*

State dimensions of freeing port area on back of this form.

The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft, should be reported.

§ If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.

† In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.

§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and sternpost. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and stern-post.

† State dimensions of freeing port area on back of this form.

† The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft, should be reported.