

Lloyd's Register of Shipping.

Ship's Name "EMPIRE FORTUNE" Official No. 169049.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

In connection with the provision of additional accommodation in the 'tween deck aft starbd. side, the following have been fitted:

Ventilators - 2 cowls, with coamings 3'-0" high, 8 1/2" dia x 5/16" thick.

3 G.N.V's, 6" dia, 2'-6" high to mouth.

Wood plugs + canvas covers provided.

Lidescuttles having hinged deadlights fitted thro' ship's side.

Sanitary discharges - W.C. discharge fitted with automatic N.R. valve on ship's side having positive means of closing it from a position above the freeboard deck.

Washplace discharge + messroom sink discharge both fitted with 2 automatic N.R. valves on ship's side, the inboard valves are always accessible for examination.

G. Campbell.

Newcastle-on-Tyne.

20th Feb. 1943.

a copy of the above has not been placed on board.

Note - A 2nd deck scupper has been fitted in washplace starbd. side aft 'tween deck, having one automatic N.R. valve on ship's side. This scupper has been blanked off at the deck, on account of positive means of closing operated from above the freeboard deck, not having been provided. It is recommended that this scupper be not used until suitable means of control has been provided.

(Report & forwarded.)