

COPY.

Lloyd's Register of Shipping.



Port of Düsseldorf.

25th August 1933.

Order: ER.5384/S.20660.

This is to Certify that

F r a n z S c h n e l l

the undersigned Surveyor to this Society did at the request of Messrs. Mannesmannröhren-Werke Abt. Walzwerk of Düsseldorf-Rath test and inspect on the 11th and 17th August 1933 at their work the undermentioned seamless Siemens-Martin Steel deckpillar tubes, ordered by Messrs. Odense Staalskibsværft of Odense and destined for the vessel No.50.

S p e c i f i c a t i o n .

deckpillar tubes...	190mm	outs.diam...	7,75mm	thickn.of shell,	3050mm	of length		
"	"	...203mm	"	"	3050mm	"	"	"
"	"	...178mm	"	"	3050mm	"	"	"

R e s u l t s o f t e s t s .

Sample No.	Tensile ten. in kg.p.sq.mm.	Elongation in 200mm
10	55,3	15,0%
13	55,0	15,0%
14	56,3	18,0%
11	55,1	20,0%
12	57,2	15,5%

Bend tests good.

The deckpillar tubes have been inspected internally and externally and were found, so far as can be seen, sound and free from surface defects.

Identification marks: Charge No. L.R. and F.S.

Fees: £ 2:0:0
 Expenses: £ 0:2:0
 Total: £ 2:2:0

J. Schnell
Surveyor to Lloyd's Register

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

“ While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Committee or any Member thereof, or the Surveyors, or other Officers or Agents of the Society.”

