

Lloyd's Register of Shipping.

Ship's Name "TARONGA".

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in April 1948.

Freeing ports (p& s) in tonnage well permanently closed. ✓

An overboard scupper of 5" diameter fitted on each side of the tonnage well with a screw down automatic non return valve controlled from the shelter deck and having an indicator showing whether the valve is open or closed. ✓

Maindeck scupper pipes removed and opening in deck and shell permanently closed. and shelter tween deck drained to engine room bilges by scupper pipes on each side and fitted with self closing weighted cocks. ✓

All bulkheads in shelter deck tweendeck fitted with draining holes as required. ✓

SURVEYOR TO LLOYD'S REGISTER-ANTWERP.

C. J. Baerendonck

*Copies: 1 on board
1 to O/S Surveyor.*

Noted
4 - MAY 1948