

Mr. Platt  
FREEBOARD REPORT on the Messrs. Hawthorn, Leslie & Co. Ltd. Yards N.596.

Memo. for Mr. Watt in answering Mr. Webster's letter of 3rd. inst.

- 1). Increasing length of forecastle (closed) by two frame spaces gives a summer freeboard of 15.82".
- 2). Increasing length of forecastle (closed) by one frame space & increasing sheer (parabolic) forward so that end ordinate is 70 inches gives a summer freeboard of 16.03".
- 3). Increasing sheer forward (parabolic) so that end ordinate is 80" gives a summer freeboard of 16.04".

87. B. Lloyd's Register  
5-12-24 Foundation

003252-003262-0023